

AD-A156 232


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
LAKE KANASATKA DAM (N. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV MAR 80


1/1

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00125	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Lake Kanastka Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE March 1980
		13. NUMBER OF PAGES 45
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Moultonboro, New Hampshire Tributary to Lake Winnepesaukee		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) → The dam consist of an earth embankment with a stoplog controlled sluiceway type spillway. The dam is in good condition. It is intermediate in size with a significant hazard potential. There are various remedial measures which must be implemented immediately. ←		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF
NEDED

JUL 23 1980

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

Inclosed is a copy of the Lake Kanastota Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,

MAX B. SCHEIDER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

MERRIMACK RIVER BASIN
MOULTONBORO, NEW HAMPSHIRE

LAKE KANASATKA DAM
NH 00125

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Inspection For	
Phase I GRA&I	<input checked="checked" type="checkbox"/>
Phase II TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Small caliber	
Dist	Special
A-1	23
CW	

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

MARCH 1980

NATIONAL DAM INSPECTION PROGRAM
PHASE I INVESTIGATION REPORT

Identification No.:	NH 00125
Name of Dam:	Lake Kanasatka
Town:	Moultonboro
County and State:	Carroll, New Hampshire
Stream:	Tributary to Lake Winni- pesaukee
Date of Site Visit:	1 November 1979

BRIEF ASSESSMENT

Lake Kanasatka Dam consists of an earth embankment with a stoplog controlled sluiceway type spillway. The box culvert of the sluiceway is about 104 ft. long. The embankment forms part of New Hampshire Route 25. The crest length of the dam is estimated to be 240 ft. with an associated height of 17 ft. The dam was constructed as part of a federally funded realignment of Route 25 in 1954. Lake Kanasatka serves primarily as a recreational reservoir though a measure of flood protection is obtained through seasonal operation of the sluiceway.

Due to the extent of downstream development that would be affected in the event the dam were to fail, Lake Kanasatka Dam has been determined to have a "significant" hazard potential classification in accordance with the Corps of Engineers guidelines.

The dam is in good condition, based on a visual examination of the structure. Although a few deficiencies were noted, there was no evidence of settlement, lateral movement or other signs of structural failure, or conditions which would warrant urgent remedial action.

Based on the "intermediate" size and "significant" hazard potential classifications, in accordance with Corps of Engineers guidelines, the adopted test flood for this dam is 1/2 the Probable Maximum Flood (1/2 PMF). With the water level at the top of dam, the spillway capacity is approximately 740 cfs with all stoplogs removed. Hydraulic analyses indicate that the routed test flood outflow of 660 cfs (inflow 7,660 cfs or 1,050 csm) could be passed with a freeboard of about 1.5 ft. and an unused surcharge-storage of about 640 acre-ft. remaining.

The New Hampshire Water Resources Board, owner of the

dam, should conduct an investigation of the need for trash racks at the upstream end of the sluiceway, as outlined in Section 7.2. This investigation should be performed under the direction of a registered professional engineer qualified in the design and construction of dams. Any necessary modifications resulting from the investigation, and remedial measures, including clearing the discharge channel, fixing the leak in the box culvert and providing a means of access to the sluiceway stop-logs during high reservoir stages, as outlined in Section 7.3. This work should be implemented by the Owner within two years after receipt of this report. The Owner should also prepare a formal operations and maintenance manual for the dam and establish an emergency preparedness plan and downstream warning system that would compliment the State's existing disaster operations plan, "Link-Up".

HALEY & ALDRICH, INC.
by:



Harl Aldrich
President



This Phase I Inspection Report on Lake Kanasatka Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

Carney M. Terzian

CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division

Richard J. DiBuono

RICHARD DIBUONO, MEMBER
Water Control Branch
Engineering Division

Aramast Mahtesian

ARAMAST MAHTESIAN, CHAIRMAN
Geotechnical Engineering Branch
Engineering Division

APPROVAL RECOMMENDED:

Joe B. Fryar

JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the office of Chief of Engineers, Washington, DC 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I Investigations are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the test flood is based on the estimated "probable maximum flood" for the region (greatest reasonably possible storm run-off), or a fraction thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential. Consideration of downstream flooding other than in the event of a dam failure is beyond the scope of this investigation.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>ction</u>	<u>Page</u>
LETTER OF TRANSMITTAL	
BRIEF ASSESSMENT	
VIEW BOARD PAGE	
REFACE	i-ii
TABLE OF CONTENTS	iii-v
INTERVIEW PHOTO	vi
LOCATION MAP	vii

REPORT

PROJECT INFORMATION

1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-3
f. Operator	1-3
g. Purpose of Dam	1-3
h. Design and Construction History	1-3
i. Normal Operational Procedures	1-4
1.3 Pertinent Data	1-4

ENGINEERING DATA

2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

VISUAL EXAMINATION

3.1 Findings	3-1
--------------	-----

TABLE OF CONTENTS

	<u>Page</u>
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-2
e. Downstream Channel	3-3
3.2 Evaluation	3-3
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	4-1
a. General	4-1
b. Description of any Warning System in Effect	4-1
4.2 Maintenance Procedures	4-1
a. General	4-1
b. Operating Facilities	4-1
4.3 Evaluation	4-1
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General	5-1
5.2 Design Data	5-1
5.3 Experience Data	5-1
5.4 Test Flood Analysis	5-1
5.5 Dam Failure Analysis	5-2
6. EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observations	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-1
6.4 Seismic Stability	6-1
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	7-1

ently sloping wooded terrain. The shoreline is generally developed with summer cottages. There is no significant probability of landslides into the reservoir affecting the safety of the dam. No conditions were noted that could result in a sudden increase in sediment load into the reservoir.

e. Downstream Channel. An unnamed brook conveys discharge from the dam approximately 1,800 ft. to the Blackey Cove portion of Lake Winnepesaukee. The elevation difference between the normal water surfaces of Lake Kanasatka and Lake Winnepesaukee is approximately 11 ft. Existing development along the downstream channel is presently limited to the shoreline of Blackey Cove to the west of the mouth of the downstream channel.

The downstream channel contains some loose stones immediately downstream of the sluiceway outlet. There was also minor debris in the form of tree branches noted in the channel at the same location.

.2 Evaluation

Based on the visual examination conducted on 1 November 1979, Lake Kanasatka Dam is considered to be in good condition. However, the remedial measures outlined in Section .3 should be implemented to correct the noted deficiencies in the sluiceway culvert and downstream channel.

the right wingwall of the outlet and dry-laid stone wall immediately downstream of the right wingwall.

The masonry portion of Lake Kanasatka Dam (the sluiceway) is in good condition. However, it was found during the site inspection that the dimensions of the sluiceway inlet structure, Photo No. 2, are not as shown on the design plans furnished by the New Hampshire Water Resources Board. In particular, the maximum height available for stoplogs is 8 ft. and not 10 ft. as shown on the design plans.

It was also found that the sluiceway culvert consists of two distinct parts with different cross-sections, Photo No. 9. From the inlet, 62 ft. of the culvert length is of old construction and measures approximately 7.5 ft. by 7.5 ft. in section. The old construction meets an 8 ft. by 8 ft. section that extends to the outlet. Instead of rebuilding the entire length of the culvert during the 1954 reconstruction of the facility, the then existing culvert was apparently extended with the enlarged section.

Clear seepage into the culvert was detected at the junction of its two sections, about 6 in. above the base slab on the right side. The taped length of the culvert, from the downstream end of the stilling pool at the inlet to the outlet, is 103 ft.

Minor erosion of concrete along the base slab of the older portion of the culvert and minor distress at the junction of the old and new portions were apparent. The concrete, especially at the newer portions of the facility, appeared to be sound and without deficiencies. The alignment of the structural elements, with the exception of the first monolith of the discharge conduit from the upstream end, was good with no indication of settlement. The first monolith did not indicate any recent movement and its slightly tilted condition is probably due to an original construction error.

Conditions at the sluiceway outlet, including wingwalls, are excellent, Photo No. 8. Rehabilitation work performed by the New Hampshire Department of Public Works and Highways in 1976 is evident. The stone masonry walls at either side of the outlet are in satisfactory condition.

c. Appurtenant Structures. There are no separate appurtenant structures for the facility.

d. Reservoir Area. Lake Kanasatka is bordered by

SECTION 3 - VISUAL EXAMINATION

3.1 Findings

a. General. The Phase I visual examination of Lake Kanasatka Dam was conducted on 1 November 1979. The upstream water surface elevation was about 4.1 ft. below the top of the sluiceway inlet structure that day or at about full pond elevation. The top two stoplogs had been removed from the sluiceway the day before the site examination.

In general, the project was found to be in good condition. A few deficiencies which require correction were noted.

A visual inspection check list is included in Appendix A and selected photographs of the project are given in Appendix C. A "Site Plan Sketch", page C-1, shows the direction of view for each photograph.

b. Dam. The upstream slope of the earth embankment is covered partly by mown grass and some areas are bare with exposed sandy gravelly fill material, Photos Nos. 2 and 7. Weeds, tall grass and small brush cover portions of the slope in areas away from the sluiceway inlet, Photo No. 4. Minor erosion of the upstream slope is occurring to the right of the sluiceway inlet, Photo No. 3. This erosion is caused by local runoff and extends about 30 ft. up the slope, Photo No. 2.

The bare sandy gravelly areas were part of a prior alignment of New Hampshire Route 25, and presently form a small parking area. Remnants of the old pavement are locally visible. Erosion from vehicles traveling on the embankment is evident, Photo No. 5, but not considered serious.

The horizontal alignment of the crest is straight. The crest elevation varies along the vertical curve for the highway, Photo No. 6. The roadway pavement covering the crest of the dam is in generally good condition. There are several transverse cracks in the pavement, the largest of which is about 1/8 in. in width.

On the downstream side, the embankment is covered with tall grass as shown on Photo No. 1. There is some erosion, less than 3 in. deep and 1 ft. wide, to the left of the sluiceway outlet. Also, there are minor bare areas behind

SECTION 2 - ENGINEERING DATA

2.1 Design Data

No design data for the dam and mill that occupied the site prior to 1937 were located and none are believed to exist. New Hampshire Route 25 was rehabilitated in 1937 and again in 1954. Plans for both reconstructions were located and in general show the enlargement and lengthening of the sluiceway culvert and changes in the roadway alignment. The above plans comprise all the available design data known to exist.

2.2 Construction Data

No as-built data or records of the reconstruction of the embankment and sluiceway in 1954 were located and none are believed to exist.

2.3 Operation Data

No operational data, other than prior inspection reports, were located for the facility.

2.4 Evaluation of Data

a. Availability. A list of the engineering data available for use in preparing this report is included on page B-1. Selected documents from the listing are also included in Appendix B.

b. Adequacy. There was a considerable amount of engineering data available to aid in the evaluation of Lake Kanasatka Dam. A review of these data in combination with visual examination, preliminary hydraulic and hydrologic computations, consideration of past performance and application of engineering judgement, was adequate for the purposes of a Phase I assessment.

c. Validity. The information contained in the engineering data may generally be considered valid. However, details on the drawings are shown as designed and vary from those actually built. For example, the configuration of the sluiceway inlet and internal dimensions for an upstream section of the box culvert are not as shown on the 1953 design drawings.

- 5. U/S channel..... Lake Kanasatka; flared headwall forms approach to sluiceway
- 6. D/S channel..... Small unnamed brook at $S = 0.003$ to Lake Winnepesaukee
- 7. General..... D/S channel has sufficient capacity to convey test flood

j. Regulating Outlets. The sluiceway has a 7 ft. wide stoplog bay which regulates low flow discharges. The sill elevation of the stoplog bay is 1.0 ft. above the upstream invert elevation of the box culvert. If all stoplogs are removed, the recreational pond water surface elevation (El. 515.0) can be lowered 4.0 ft.

e. Storage (acre-ft.)

1. Recreation pool..... 1,620 at El. 515.0
2. Flood control pool..... Not applicable
3. Winter pool..... 1,240 at El. 514.1
4. Top of dam..... 5,640 at El. 524.0
5. Test flood pool
 all stoplogs removed..... 5,000 at El. 514.1
 stoplogs to El. 515.0..... 5,220 at El. 523.1

f. Reservoir Surface (acres)

1. Recreation pool..... 392
2. Flood control pool..... Not applicable
3. Winter pool..... 371
4. Top of dam..... 527
5. Test flood pool (all stop-
 logs removed)..... 505

g. Dam

1. Type..... Earth fill (roadway
 embankment)
2. Crest length..... 240 ft. (Est.)
3. Height..... 17 ft.
4. Crest width..... 48 ft.
5. Side slopes..... Irregular
 U/S 10H to 1V;
 D/S 1.5H to 1V
6. Zoning..... Unknown
7. Impervious core..... Unknown
8. Cutoff..... Unknown
9. Grout curtain..... None
10. Other..... Crest of dam paved; New
 Hampshire Route 25

h. Diversion and Regulating Tunnel Not applicable

i. Spillway

1. Type..... Stoplog controlled sluice-
 way
2. Length of weir..... 7.0 ft.
3. Crest elevation (all stop-
 logs in place)..... 515.0
4. Gates..... None (stoplogs are main-
 tained at a maximum of
 5.0 ft. in height above
 invert of box culvert)

2. Maximum known flood at dam site..... 4 July 1973 maximum lake level estimated at El. 521.3
3. Ungated spillway capacity at top of dam (all stoplogs removed)..... 740 cfs at El. 524.0
4. Ungated spillway capacity at test flood pool elevation (all stoplogs removed)..... 660 cfs at El. 522.5
5. Gated spillway capacity at top of dam (stoplogs to El. 515.0)..... 230 cfs at El. 524.0
6. Gated spillway capacity at test flood pool elevation (stoplogs to El. 515.0)..... 220 cfs at El. 523.1
7. Total spillway capacity at test flood pool elevation (all stoplogs removed)..... 660 cfs at El. 522.5
8. Total project discharge at test flood pool elevation (all stoplogs removed)..... 660 cfs at El. 522.5

c. Elevation (ft. above NGVD)

1. Streambed at centerline of dam..... 507.0
2. Maximum tailwater..... Unknown
3. Upstream portal invert diversion tunnel..... Not applicable
4. Recreation pool..... 515.0
5. Full flood control pool..... Not applicable
6. Spillway crest
 - without stoplogs..... 511.0
 - with stoplogs - winter..... 514.1
 - with stoplogs - summer..... 515.0
7. Design surcharge - original design..... Unknown
8. Top of dam..... 524.0
9. Test flood surcharge
 - all stoplogs removed..... 522.5
 - stoplogs to El. 515.0..... 523.1

d. Length of Reservoir (mi. estimated)

1. Recreation pool..... 2.0
2. Flood control pool..... Not applicable
3. Winter pool..... 2.0
4. Top of dam..... 2.1
5. Test flood pool (all stoplogs removed)..... 2.1

reconstruction of the roadway titled "Federal Aid Project No. 315-A, Whittier Road". The configuration of the then existing roadway and modifications planned for the project realignment are shown on Sheet No. 5 of these drawings (see Appendix page B-11).

The present earth embankment and sluiceway were designed in 1953 as part of a federally funded realignment of Route 25. Construction of the project, to its present configuration and alignment, (see Appendix page B-13), was completed in 1954.

In 1976 the New Hampshire Department of Public Works and Highways, Maintenance Division 03, rehabilitated portions of the box culvert endwall and downstream channel, (see Appendix pages B-7 and B-8). No plans of this work exist.

i. Normal Operational Procedures. There is no formal written procedure for the operation of Lake Kanasatka Dam. The sluiceway is operated seasonally to control the spring freshet. The wooden stoplogs, which may be removed in times of emergency or high runoff and discharge, are maintained by the State. The normal operating procedure is to lower the recreational pond level approximately 0.9 ft. during the winter and spring by removing two stoplogs. The resulting winter pool elevation is 514.1 and the summer (recreational) pool elevation is 515.0. It is understood that the dam is periodically inspected by the Owner.

1.3 Pertinent Data

All elevations reported herein are based on or were measured relative to a reservoir elevation given on the USGS Winnepesaukee Quadrangle Map. By comparison with information obtained from the files of the New Hampshire Water Resources Board, it appears reasonable to assume the given elevation is correct and that the elevations presented in this report are based on National Geodetic Vertical Datum (NGVD).

a. Drainage Area. The drainage area tributary to the dam site is 7.3 sq. mi. The southwestern portion of the watershed is sparsely developed rolling to mountainous terrain and the north-eastern portion (Red Hill) is steeply sloped, heavily forested, undeveloped terrain, all of which drains to Wakondah Pond (upstream of Lake Kanasatka) and to Lake Kanasatka. The normal water surface area of Lake Kanasatka represents about 8 percent of the total drainage area and the surcharge area (water at top of dam) about 10.5 percent. The water surface area of Wakondah Pond is about 4 percent of the total drainage area.

b. Discharge at Dam Site

1. Outlet works (all stoplogs removed)..... 150 cfs with lake at normal pool El. 515.0

two homes located approximately 1,800 ft. downstream of the dam on the shore of Lake Winnepesaukee. Although the homes are located on the fringe of the impact area, one of the homes could be flooded by up to 4 ft. of water.

e. Ownership. The name, address and phone number of the current owner of Lake Kanasatka Dam are:

Water Resources Board
State of New Hampshire
37 Pleasant Street
Concord, New Hampshire 03301
Phone: (603) 271-3406

Mr. Vernon A. Knowlton is the Chief Engineer of the Water Resources Board.

The Department of Public Works and Highways has the responsibility of maintaining New Hampshire Route 25 and in turn monitors the condition of the roadway and embankment on an informal basis. Mr. Kenneth Kyle with the Department of Public Works can be reached at the following address and phone number:

Department of Public Works and
Highways
Maintenance Division 03
State of New Hampshire
P.O. Box 99
Laconia, New Hampshire 03246
Phone: (603) 524-6667

f. Operator. The Water Resources Board of the State of New Hampshire has been responsible for operation, maintenance and safety of the dam since about 1954. The Board may be reached at the address and phone number listed above. The Water Resources Board does not designate a particular individual as operator of a specific dam but operates all state-owned dams by their staff of engineers and operators on a continual basis.

g. Purpose of Dam. Lake Kanasatka serves as a large recreational reservoir. A measure of flood protection is obtained through seasonal operation of the sluiceway.

h. Design and Construction History. Prior to 1937 the site was occupied by a mill and an associated dam. The type of mill and year abandoned are unknown. The only record of the mill's existence is on 1937 drawings for the

of the dam site are $N43^{\circ}42.9'$ and $W71^{\circ}26.7'$, respectively.

Spillway discharge is conveyed by an unnamed brook approximately 1,800 ft. to Blackey Cove, an inlet at the northwestern end of Lake Winnepesaukee. Lake Winnepesaukee is tributary to the Merrimack River Basin.

b. Description of Dam and Appurtenances. Lake Kanasatka Dam consists of an earth embankment with a stoplog controlled box culvert, or sluiceway, type spillway. The crest of the embankment is paved and forms part of New Hampshire Route 25, or Whittier Road. The crest length of the dam is estimated to be 240 ft. with an associated height of 17 ft. The crest is about 48 ft. wide.

On the upstream side, from the sluiceway to the roadway shoulder for a distance of about 45 ft., the ground slopes gently at about 10 horizontal to 1 vertical. At the location of the dam, the Route 25 roadway is about 25 ft. wide with 8 to 9-ft. wide paved shoulders. The distance from the sluiceway endwall to the roadway shoulder is approximately 14.5 ft. The downstream slope of the embankment in the area of the sluiceway outlet is about 1.5 horizontal to 1 vertical. There are dry-laid stone walls at the ends of both the right and left concrete wingwalls that line the downstream channel at the outlet.

The inlet, culvert and outlet are all concrete. The culvert is 104 ft. long and traverses the embankment, in a slightly skewed alignment, about 160 ft. from the right end of the dam. The elevation difference from the top of the sluiceway at the inlet to the low point of the embankment, or top of dam, is approximately 5 ft.

c. Size Classification. The storage to the top of Lake Kanasatka Dam is estimated to be 5,640 acre-ft., and the corresponding height of the dam is approximately 17 ft. Storage of from 1,000 to 50,000 acre-ft. and/or a height of from 40 to 100 ft. classifies a dam in the "intermediate" size category, according to guidelines established by the Corps of Engineers. Although the height of this dam is much less than 40 ft., it is classified as an "intermediate" size dam by virtue of its storage capacity.

d. Hazard Classification. Dam failure analysis computations in Appendix D, which are based on Corps of Engineers "Guidance for Estimating Downstream Dam Failure Hydrographs", demonstrates why this dam has been determined to have a "significant" hazard potential classification. A failure of the dam could cause the loss of a few lives to the inhabitants of

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

LAKE KANASATKA DAM
NH 00125

SECTION 1 - PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region.

Haley & Aldrich, Inc. has been retained by the New England Division to inspect and report on selected dams in the States of New Hampshire and Maine. Authorization and notice to proceed were issued to Haley & Aldrich, Inc. under a letter dated 31 October 1979 from Colonel William E. Hodgson, Jr., Corps of Engineers. Contract No. DACW33-80-C-0009 has been assigned by the Corps of Engineers for this work. Camp, Dresser & McKee, Inc. was retained as consultant to Haley & Aldrich, Inc. on the structural, mechanical/electrical and hydraulic/hydrologic aspects of the Investigation.

b. Purpose of Inspection. The primary purposes of the National Dam Inspection Program are to:

1. Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

2. Encourage and prepare the states to initiate effective dam safety programs for non-Federal dams.

3. Update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. The dam is located at the southern end of Lake Kanasatka in Moultonboro, New Hampshire, as shown on the Location Map, page vii. The latitude and longitude



1. Overview of Lake Kanasatka Dam showing downstream side

TABLE OF CONTENTS

	<u>Page</u>
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
a. Operation and Maintenance Procedures	7-1
7.4 Alternatives	7-2
APPENDIX A - INSPECTION CHECKLIST	A-1
APPENDIX B - ENGINEERING DATA	B-1
APPENDIX C - PHOTOGRAPHS	C-1
APPENDIX D - HYDRAULIC AND HYDROLOGIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1

SECTION 4 - OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

a. General. In general, there are no formal procedures for the operation of the dam. The stoplogs are normally maintained at full pond level (El. 515.0) during the summer and fall and approximately 0.9 ft. lower (two stoplogs removed) during the winter and spring. The Owner's instruction for emergency operations state, "pull stoplogs as required, if possible". The dam is visited three times a week by a New Hampshire Water Resources Board Operator and checked once a year by their maintenance group.

b. Description of any Warning System in Effect. There is no specific warning system or emergency preparedness plan in effect for this structure. However, the Owner is within the framework of the operations plan "Link-Up", an inter-agency plan in the State of New Hampshire for natural and man-made disaster operations. The plan establishes the procedure for notifying and calling upon the resources of other state agencies in times of emergency.

4.2 Maintenance Procedures

a. General. There are no established procedures or manuals for inspection and maintenance of the dam. Remedial measures such as the replacement of stoplogs and repairs to the box culvert are performed on an as needed basis.

b. Operating Facilities. The spillway structure appears to have received regular maintenance. There is no formal plan to maintain the stoplogs or keep the outlet works free of debris. Two stoplogs were inserted and removed during the site inspection and no conditions were observed which would hinder the removal of all stoplogs with pond at normal elevation. However, stoplog removal during flood stages greater than 4 ft. above normal pond level could be difficult and dangerous.

4.3 Evaluation

The Owner should prepare an operations and maintenance manual for the dam. The manual should delineate the routine operational procedures and maintenance work to be done on

the dam to provide satisfactory operation and minimize deterioration of the facility. For example, an annual observation and maintenance program should be established to examine the dam, control vegetation growth and maintain slopes, walls and channels. A formal procedure should be established for the removal of stoplogs during flood conditions.

Since failure of the dam would probably cause loss of life and property damage downstream, the owner should also prepare and implement a formal emergency preparedness plan and warning system for the specific dam to compliment the existing operations plan "Link-Up".

SECTION 5 - EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 General

Lake Kanasatka Dam is a recreation pond dam approximately 240 ft. long. The sluiceway, or outlet works, consists of a stoplog regulated box culvert. The stoplog bay is 7 ft. long with a maximum stoplog height of 4 ft. The upstream end of the box culvert is approximately 7.5 ft. square and its entrance invert is 1.0 ft. below the stoplog sill elevation. The dam is basically a high surcharge-low spillage facility having a 9 ft. freeboard between normal pond level and top of dam which results in an available surcharge storage of about 4,000 acre-ft. Discharges from the outlet works are conveyed approximately 1,800 ft. by an unnamed brook to the Blackey Cove portion of Lake Winnepesaukee. The southwest side of Red Hill (20 percent slope) constitutes about 35 percent of the total 7.3 sq. mi. drainage area. The normal water surface area of Lake Kanasatka represents approximately 8 percent of the total watershed.

5.2 Design Data

There is no hydraulic/hydrologic design data available for the dam.

5.3 Experience Data

No records of historical floods were located for the dam site. According to the New Hampshire Department of Public Works and Highways, the most significant flood in recent years occurred on 4 July 1973 when the Lake reached an estimated stage of 2 ft.-3 in. above the top slab of the inlet structure (estimated surcharge El. 521.3). Since the inlet control conditions during that event are unknown (i.e.: number of stoplogs in place and amount of debris), it is not possible to estimate the peak discharge from the dam.

5.4 Test Flood Analysis

Based on the Corps of Engineers Guidelines, the recommended test flood range for the size "intermediate" and hazard potential "significant" is the 1/2 PMF to the PMF (Probable Maximum Flood). The 1/2 PMF was adopted as the

test flood for the facility as the size is near the low end of the classification range. The 1/2 PMF was determined using the Corps of Engineers Guidelines for "Estimating Maximum Probable Discharge" in Phase I Dam Safety Investigations. The 7.3 sq. mi. drainage area includes the steeply sloped, undeveloped southwest side of Red Hill which drains to Lakes Wakondah and Kanasatka. A peak inflow rate of 1,050 csm based on the Guidelines' "mountainous" curve was selected for the 1/2 PMF which results in test flood inflow of 7,660 cfs.

Surcharge storage routing of the test flood inflow, assuming all stoplogs are in place initially and then removed when the water level rises to the bottom of the inlet platform, resulted in a routed test flood outflow of 660 cfs at a stage elevation of 522.5. The drastic reduction between inflow and outflow (7,660 cfs vs. 660 cfs) is a function of the limited discharge capacity of the box culvert together with the abundance of available surcharge storage between normal pond level and top of dam. Furthermore, surcharge storage routing of the test flood inflow, assuming that no stoplogs are removed, results in a routed test flood outflow of 220 cfs at El. 523.1. Since the top of dam is at El. 524.0, the facility is considered hydraulically adequate to pass the test flood without overtopping the dam. It should be recognized, however, that a test flood stage of about 8 ft. above normal pool would result in extensive damage to properties located along the reservoir shoreline.

5.5 Dam Failure Analysis

Based on the Corps of Engineers guidelines for estimating dam failure hydrographs, and assuming that a failure would occur along 40 percent of the mid-height length of the dam, the peak failure outflow is estimated to be 4,700 cfs in addition to the 740 cfs outlet works discharged occurring prior to failure. As a result of a dam failure, Route 25 would be rendered impassable and 2 to 3 homes located near the mouth of the discharge channel along the shore of Lake Winnepesaukee and the fringe of the impact area would be subject to shallow depth-high velocity flooding less than 2 ft. in depth. Furthermore, additional future development of the potential impact area appears likely.

The potential loss of life resulting from a dam failure is a few and the dam is accordingly classified in the "significant" hazard category.

SECTION 6 - EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations

There was no visual evidence of ongoing settlement, lateral movement or other signs of structural instability in the earth embankment or sluiceway of this dam. Based on the conditions observed during the visual examination of the facility, no reason was found to question the structural stability of this facility.

6.2 Design and Construction Data

No plans were located for the construction of the original dam that occupied the site prior to 1937. Plans for the 1937 and 1954 reconstructions of the facility were located at the New Hampshire Department of Public Works and Highways, Maintenance Division 03, in Laconia, New Hampshire. Though no detailed stability analyses are available, the general dimensions of the embankment and sluiceway are within the range of what usually would be expected for stable structures of this size. For this reason, combined with conditions observed during the site examination, the dam is expected to have an adequate factor of safety relative to overall stability.

6.3 Post-Construction Changes

The discharge end of the sluiceway was renovated in 1976 as discussed in Section 1.2h. Nothing is known about possible other post-construction changes at this facility.

6.4 Seismic Stability

Lake Kanasatka is located in a Seismic Zone 2 and in accordance with Recommended Phase I Guidelines does not warrant seismic analysis.

SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination of Lake Kanasatka Dam revealed that the structure was in good condition. Although there were no signs of impending structural failure or other conditions which would warrant urgent remedial action, a few deficiencies were noted.

Based on the results of computations included in Appendix D and described in Section 5, the spillway is capable of passing the test flood, which for this structure is the 1/2 PMF, without overtopping the dam. With the water level at the top of the dam, the spillway capacity is approximately 740 cfs with all stoplogs removed. The routed test flood outflow of 660 cfs (inflow of 7,660 cfs or 1,050 csm) could be passed with a freeboard of about 1.5 ft. and an unused surcharge-storage of about 640 acre-ft. remaining.

b. Adequacy of Information. This evaluation of the dam is based primarily on visual examination, preliminary hydraulic and hydrologic computations, consideration of past performance and application of engineering judgement. Generally the information available or obtained was adequate for the purposes of a Phase I assessment.

c. Urgency. The recommendations for remedial measures outlined in Section 7.3 should be undertaken by the Owner and completed within two years after receipt of this report.

7.2 Recommendations

It is recommended that an investigation of the need for trash racks at the upstream end of the sluiceway be conducted. This investigation should be performed under the direction of a registered professional engineer qualified in the design and construction of dams. The Owner should then implement corrective measures on the basis of this engineering investigation.

7.3 Remedial Measures

Although the dam is generally in good condition, it is considered important that the following items be accomplished.

a. Operation and Maintenance Procedures. The following should be undertaken by the Owner:

1. Reset loose stones from the training wall and remove debris from the discharge channel immediately downstream of the sluiceway outlet.
2. Plug the leak on the right side wall of the box culvert where the newer section joins the older section.
3. Provide a means of access to and removal of the sluiceway stoplogs during high reservoir stages.
4. Prepare an operations and maintenance manual for the dam. The manual should include provisions for biennial technical inspection of the dam and for surveillance of the dam during periods of heavy rainfall or flood conditions. The procedures should delineate the routine operational procedures and maintenance work to be done on the dam to ensure safe, satisfactory operation and to minimize deterioration of the facility.
5. Develop a written emergency preparedness plan and warning system to compliment the existing disaster operations plan "Link-Up" to be used in the event of impending failure of the dam or other emergency conditions. The plan should be developed in cooperation with local officials and downstream inhabitants.

7.4 Alternatives

There are no practical alternatives to the above recommendations.

APPENDIX A - INSPECTION CHECK LIST

	<u>Page</u>
<u>VISUAL INSPECTION PARTY ORGANIZATION</u>	A-1
<u>VISUAL INSPECTION CHECK LIST</u>	
Dam Embankment	A-2
Outlet Works - Intake Structure	A-3
Outlet Works - Conduit	A-3
Outlet Works - Outlet Structure and Outlet Channel	A-4

VISUAL INSPECTION PARTY ORGANIZATION

NATIONAL DAM INSPECTION PROGRAM

Dam: Lake Kanasatka

Date: 1 November 1979

Time: 0745-0945

Weather: Clear and cold, (approximately 32°F)

Water Surface Elevation Upstream: El. 515 (Assumed same as shown
on USGS Map)
(4.1 ft. below top of concrete
at spillway inlet)

Stream Flow: Unknown

Inspection Party:

Harl P. Aldrich, Jr.	- Soils/Geology
Charles R. Nickerson	
Haley & Aldrich, Inc.	
Roger Wood	- Structural Mechanical
Joseph E. Downing	- Hydraulic/Hydrologic
Camp, Dresser & McKee, Inc.	

Present During Inspection:

Kenneth T. Stern, N.H. Water Resources Board
Kenneth Kyle, N.H. Department of Public Works and Highways

VISUAL INSPECTION CHECK LIST

NATIONAL DAM INSPECTION PROGRAM

DAM: Lake Kanasatka

DATE: 1 Nov. 1979

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	El. 524.1 (approximately at low point, left end)
Current Pool Elevation	El. 515 (Assumed as shown on USGS topographic sheet)
Maximum Impoundment to Date	Unknown
Surface Cracks	None observed
Pavement Condition	Excellent; several minor transverse cracks not more than 1/8 in. wide
Movement or Settlement of Crest	None observed; pavement smooth
Lateral Movement	None observed
Vertical Alignment	Roadway grade varies; low point at left end of dam
Horizontal Alignment	Good
Condition at Abutments and at Concrete Structures	Satisfactory
Indications of Movement of Structural Items on Slopes	No structural items on slopes
Trespassing on Slopes	Unrestricted; very common on gentle upstream slope
Animal Burrows in Embankment	None observed
Vegetation on Embankment	Upstream slope bare over a large area; mowed grass at left end; weeds at right end. Downstream slope weeds and grass; few small bare areas
Sloughing or Erosion of Slopes or Abutments	Considerable erosion beyond paved shoulder of roadway on upstream side right of spillway intake. Erosion of earth fill about 8 ft. directly right of intake (see text)
Rock Slope Protection - Riprap Features	No rock on upstream slope, except at waterline; not continuous
Unusual Movement or Cracking at or near Toes	None observed
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	None known to exist
Toe Drains	None known to exist
Instrumentation Systems	None

VISUAL INSPECTION CHECK LIST **NATIONAL DAM INSPECTION PROGRAM**

DAM: Lake Kanawatka

DATE: 1 Nov. 1979

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE STRUCTURE</u>	
a. <u>Approach Channel</u>	
Slope Conditions	Intake at edge of lake
Bottom Conditions	Eroded area adjacent to stop logs
Rock Slides or Falls	Not applicable
Log Boom	None
Debris	None observed
Condition of Concrete	Not applicable
Lining	
Drains or Weep Holes	None observed
b. <u>Intake Structure</u>	
Condition of Concrete	Good
Stop Logs and Slots	Good
Railing	Railing removed - stubs have been capped
<u>OUTLET WORKS - CONDUIT</u>	
General Condition of Concrete	Fair - U/S right monolith is tilted (may have been constructed that way)
Rust or Staining on Concrete	No material condition observed
Spalling	No material condition observed
Erosion or Cavitation	Surface erosion base slab
Cracking	Crack where new culvert joins older culvert. Flow of water from crack on right side (6 in. above base slab)
Alignment of Monoliths	See "General Condition of Concrete"
Alignment of Joints	Good
Numbering of Monoliths	Not applicable

A-3

VISUAL INSPECTION CHECK LIST **NATIONAL DAM INSPECTION PROGRAM**

DAM: Lake Kanasatka



DATE: 1 Nov. 1979

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - OUTLET</u> <u>STRUCTURE AND OUTLET</u> <u>CHANNEL</u></p> <p>General Condition of Concrete Rust or Staining Spalling Erosion or Cavitation Visible Reinforcing Any Seepage or Efflo- rescence Condition at Joints Drain holes Channel Loose Rock or Trees Overhanging Channel Condition of Discharge Channel</p>	<p>Excellent</p> <p>None observed None observed None observed None observed None observed</p> <p>None noted None observed Natural woodland stream Few loose rocks at left training wall. Minor debris (branches in channel) Good</p>

APPENDIX B - ENGINEERING DATA

	<u>Page</u>
<u>LIST OF AVAILABLE DATA</u>	B-1
<u>PRIOR INSPECTION REPORTS</u>	
<u>Date</u>	<u>Description</u>
26 August 1974	Lake Kanasatka Association, Inc.
	B-3
<u>DRAWINGS</u>	
"State of New Hampshire, State Highway Department, Plan and Profile of Proposed Federal Aid Project No. 315-A, Whittier Road", Sheet No. 5, 1936	B-11
"State of New Hampshire, Department of Public Works and Highways, Plans of Proposed Federal Aid Primary Project No. F 0315 (3), N.H. No. P-2408, Whittier Road, Part A", Sheet No. 8, 1953	B-12
"State of New Hampshire, Department of Public Works and Highways, Plans of Proposed Federal Aid Primary Project No. F 0315 (3), N.H. No. P-2408, Whittier Road, Part A", Sheet No. 22, 1953	B-13

<u>Document</u>	<u>Contents</u>	<u>Location</u>
Report, Schedule of Dams, Town of Moultonboro, New Hampshire	Lists the owner's name and address for dams in Moultonboro dated 6 May 1935	Water Resources Board State of New Hampshire 37 Pleasant Street Concord, New Hampshire 03301
State of New Hampshire Public Service Commission Notice of Inspection and Inspection Report	Four items related to inspection of dams in Moultonboro on 8 July 1936	Water Resources Board State of New Hampshire
New Hampshire Water Control Commission, Data on Dams in New Hampshire	Three data sheets on inspection of dam dated 10 April 1939	Water Resources Board State of New Hampshire
Correspondence to and from the Water Resources Board	Three letters concerning possible transfer of ownership and needed repairs to dam dated from 15 September 1949 to 3 August 1953	Water Resources Board State of New Hampshire
Water Resources Board letter to Mrs. Kathryn Hall	Reply to complaint dated 28 July 1959	Water Resources Board State of New Hampshire
Army Corps of Engineers Dam Inventory Program	Two sheets with three pictures of dam dated 14 March 1974	Water Resources Board State of New Hampshire
Inspection Report by Members Lake Kanawatka Association, Inc.	Three items concerned with condition of stoplogs and dam structure dated 26 August 1974 and 8 October 1974	Water Resources Board State of New Hampshire (See Appendix page B-3 through B-6)



103

PROPOSED RECONSTRUCTION
OF
LAKE KANASATKA DAM
MOULTONBORO N.H.



DESIGNED BY L.R.F.
DRAWN BY F.S.M.
TRACED BY F. Yalowitz
CHECKED BY

NEW HAMPSHIRE WATER RESOURCES BOARD
CONCORD, N.H.


SCALE AS SHOWN OCTOBER 20, 1953 \$164.02

NONPARTICIPATING QUANTITIES FOR RECONSTRUCTION OF LAKE KANASATKA DAM AT STA 152+55 LT			
ITEM NO	61	62	321
ITEM	EARTH R	LEDGETH	CLASS A
UNIT	EXCAV R	EXCAV R	CONC
	CU YD	CU YD	CU YD
	15	10	48.27
SUB TOTAL	15	10	48.27
ESTIMATED			1.73
TOTAL	15	10	5000

THE FOLLOWING ITEMS WILL BE
CONSIDERED SUBSIDIARY TO
THE ITEM:
8-3/8" ϕ 4 1/2' LONG
2-3/4" ϕ 8' LONG
4-1/2" ϕ 1' 10' LONG
2-4" \times 3" \times 1/4" ANGLE IRONS 5.8' 10' LONG
4-4" \times 6" 1/2" STOP LOSS
4-2" STD PIPE 12' LONG W/CAPS
16-1/2" EYE BOLTS
32-1/2" FLAT WASHERS
16-1/2" SQUARE NUTS
IMPERVIOUS BACKFILL



STOP LOG
DETAILS
SCALE 1/2"=1'





DETAIL A
SCALE 1/2"=1'



DATE STA. TO STA.


DATE 11-1-55

DESIGNED BY
DRAWN BY
TRACED BY
CHECKED BY



STA 134.00 TO 134.75 L1
REMOVE SURFACE TREATMENT ITEM # 62
LOAN 2" DEEP - ITEM # 31-A





KANASATKA LAKE, MOULTONBORO 164.02


Spring - After runoff (late) fill to 12" below concrete
by June 1 . Lake is fast to fill and slow to drain

Fall - November 1 pull 2 stoplogs

EMERGENCY OPERATION: Pull stoplogs as required if possible

1. Remove stop log locks with 2402 key, and remove desired amount of stoplogs (or replace if necessary).
2. Lake reading is taken from the apron to your right when looking out on the lake, go to the far end of the apron and measure down to lake level.
3. Relock stoplogs in bays and lock extra logs to the railing.

BEFORE ANY EMERGENCY OPERATION
Call N. H. Water Resources Board
Office - 271-3406



Kanasatka Lake

Moultonboro

164.02 #

Inage Area (mi²) 7.5

i Area (Acres) 371

rage Perm. (Ac. Ft.) _____

Artificial (Ac. Ft.) 208

e reading @ Full Lake -12" concrete abutment

on gage translates to top of concrete abutment

.G.S. Elev. at full pond 514 ±

sh Flow" 0.2 cfs per mi² _____

year storm flow (cfs) _____

year storm capacity (cfs) _____

ign flow capacity (cfs) 500 capacity of culverts _____

ie to Peak (hours) _____

harge (manual-cfs) 380 with all logs removed

(automatic-cfs) 120

ilway length (ft.) 7

ilway crest elev. 510.8 (USGS)

wage of fee ownership elev. _____

od Stage (gage-ft) _____

Name _____

tracts Prior to a) # _____

eration of dam Name _____

much b) # _____

en Name _____

c) # _____

Name _____

d) # _____

stoplogs

Freeboard w/o ~~flashboards~~ (ft.) 9

stoplog

~~Flashboards~~ height (ft) 4±

stoplog

Freeboard ~~XXXXXX~~ (ft) 5

Spacing of pins (ft) _____

Number of pins _____

Design head over flashboards for automatic failure (ft) _____

Gate #1 on left/right. (circle one)

bank looking downstream _____

Number of gates _____

Size of gates _____

Gate sill elev. (gage) _____

1 Stoplog bay on right/left bank looking downstream _____

Number of stoplog bays 1

Number of S.L.'s in each bay 6

Size of each S.L. 7'7" x 4" x 8"

Elev. of sill of stoplog sect. 510.8 (MSL)

16.4" rise per inch runoff

INSTRUCTIONS TO PETITIONERS DESIRING TO FILL, DREDGE
OR PERFORM CONSTRUCTION IN WATERS OF THE STATE

1. The applicant shall submit to the Special Board two (2) copies of all application forms and inclusions.
2. Obtain signature of appropriate town or city clerk in Section 10 on all copies.
3. File three (3) copies of said application with the town/city clerk as required by Chapter 483-A.1 as amended 1973.
4. Return two (2) copies to the following address:

Mr. George M. McGee, Sr., Chairman
Special Board
Concord, New Hampshire 03301

5. The permit must be received by the applicant prior to commencement of the work and posted in a secured manner in a prominent place at the site of the approved project.

PERMIT APPLICATIONS SHALL INCLUDE AT LEAST THE FOLLOWING INFORMATION:

- a) United States Geological Survey sheet(s) (Machine copy or other facsimile acceptable) showing exact location(s) of project(s) for which a permit is being requested.
- b) A map showing the location of the project in relation to all abutters. Scales shall be appropriate for clarity.
- c) Specific directions and/or map so that inspector may drive to the site. (town, street, etc.)
- d) One detailed plan of each project drawn to scale appropriate for clarity.
- e) A complete list of abutting owners, their mailing addresses and telephone numbers, with certification that all such abutters have been notified of the project plans (not required for logging operations or highway construction).

NOTE: Repair work to consist of following items:

1. Form and place concrete along the wall/floor joints where needed.
2. Widen wing wall footings at outlet end and construct an 8" wide new face on the wing walls, and raise height of wing walls and header 2 feet.
3. Remove channel obstruction such that back water will be eliminated within the culvert (8"±). Dredged materials will be relocated to the box outlet.
4. We intend to control pollution/siltation by using baled hay just downstream of the work area.

NOTE: We intend to carry the discharge thru a 24" pipe within the box culvert during the work period. Any planned change in the current rate of discharge (or lake level) would seriously affect our plans. Our proposed schedule is flexible.

RECEIVED
CIVIL ENGINEERING DIVISION

JUL 27 1973

NEW HAMPSHIRE DEPARTMENT
OF PUBLIC WORKS & HIGHWAYS

FILL OUT ACCURATELY AND COMPLETELY TO AVOID RETURN AND DELAY

STATE OF NEW HAMPSHIRE

APPLICATION FOR PERMIT TO EXCAVATE, DREDGE,
FILL, MINE OR CONSTRUCT, IN ANY WATERS
OF THE STATE

Permit No. _____ Date _____

Hearing Required _____

Permit Approved/Denied By: _____

For the Special Board

Application is hereby made for a permit to accomplish work described below relating to excavating, dredging, or filling, in accordance with the Rules and Regulations established under the provisions of Chapter 387 of the Laws of 1969, and RSA Chapter 149:8A

1. Name of applicant (owner) N.H.D.P.W.&H., Div. 03 Telephone No. 524-6667
(please print or type)
Resident or principal business address P.O. Box 99, Laconia, NH 03246
2. Location of proposed construction
Town or City Moultonboro County Carroll
3. Adjacent to, or in 182712 (fresh) water.
4. Name of water body Outflow from Lake Kanasatka.
5. Type of project - Fill () Dredge () Wharf (X) Other Culvert Maintenance
Specify)
6. Reason(s) for proposed construction: repairs to 103' x 8' x 8' concrete
box culvert
7. (a) Proposed starting date 8/2/76 (b) Completion date 9/3/76
8. If work is to be done by self, contractor, or agent, give his name and address below:
N.H.D.P.W.&H. Maint. Division 03 Telephone Number 524-6667
(This information to be submitted prior to construction)
9. Description of construction (use reverse side for additional information):
(a) Type of material Gravel (see reverse)
(b) Estimated quantity of dredged material (cu. yd.): 50 CY
(c) Estimated quantity of fill material (cu. yd.): 50 CY
(d) Final disposition of dredged material: Restore channel
(e) If any channel is to be constructed, the distance the flow of water is to be rerouted: N/A
(f) Enclosed for your information is a copy of RSA Chapter 149:8-A, which is administered and enforced by the Water Supply and Pollution Control Commission. One copy of your application will be acted upon by the W.S.P.C.C. and such action will be incorporated in one distribution.
10. I hereby certify that the applicant has filed three (3) copies of said application with the Town/City of Moultonboro as required by Chapter 483-A.1 as amended 1973.

DATE _____

Signature _____

Town/City Clerk

11. Complete list of all abutting owners, their addresses and phone numbers: (They have been contacted and the work proposed has been explained to them. Note on separate sheet objections raised by abutters).

A permit issued under this application shall be non-transferable and shall expire two years from date of issue.

Signature of Applicant [Signature]

Date 7/26/76

NOV 20, 1973

LAKE KANASATKA WATERFED ASSOCIATION, INC.

STATUS OF ABOVE DAM WAS MADE AND ITS CONDITION IS AS FOLLOWS:

1. LAKE WATER LEVEL : 14 INCHES BELOW NORMAL LEVEL.
2. LAKE WATER LEVEL AT DAM : 4 INCHES BELOW TOP OF EXISTING BOARD.
3. LEAKS IN DAM : AT EVERY BOARD SEAM WATER IS LEAKING IN VAST AMOUNTS. AT APPROX 32 INCHES BELOW EXISTING TOP DAM BOARD A VERY LARGE LEAK IS EVIDENT (ON THE LAKE SIDE OF THIS LEAK IS A SHOE STUCK IN DAM)
4. VOLUME OF LEAKS : ESTIMATED ¹⁰⁰ 50 GAL. PER MINUTE (PLUS)
5. DAM BOARDS : MADE OF WOOD AND IN BAD CONDITION. ROT IS APPARANT ESPECIALLY AT SEAMS.
6. ROCKS AT DAM : ROCKS HAVE BEEN STACKED ON LAKE SIDE OF DAM APPARENTLY IN EFFORT TO STOP LEAKS.

HAZZARDS:

1. DAM BOARDS IN BAD CONDITION COULD GIVE AWAY AT ANY TIME.
2. BAD CONDITION OF BOARDS LOCATED BELOW THE 32 INCH LEVEL SO IF BOARDS GAVE AWAY LAKE COULD LOSE AT LEFT 4 FOOT OF WATER.
3. BOARDS CAN BE REMOVED WITH EASE. ANY ONE CAN TAMPER WITH LAKE LEVEL. EFFORT SHOULD BE MADE TO LOCK & SECURE BOARDS IN PLACE SO ONLY AUTHORIZED PERSON MAY REMOVE BOARD

RECOMMENDATIONS:

SECURE BOARDS . STOP LEAKS. RAISE BOARD LEVEL AT LEAST 12 TO 14 INCHES.

Thomas F. Dowling II

THOMAS F. DOWLING II
DEER CROSSING ROAD
MOULTONBORO, N.H.

Paul H. Schmidt

PAUL SCHMIDT
DEER CROSSING ROAD
MOULTONBORO, N.H.

MEMBERS LAKE KANASATKA ASSOCIATION, INC.





FIGURE # 2 : END VIEW - DAM AT ROUTE # 25 - LAKE KANASATKA

1. ROCKS HAVE BEEN STACKED AT APPROX BOARD 5 LEVEL
2. LEAKS AT ALL BOARD SEAMS - VERY LARGE LEAK AT BOARD 4 & 5 - A SHOE IS STUCK IN BOARD



~~SECRET~~

FIGURE # 1 : LAKE SIDE VIEW - DAM AT ROUTE # 25 - LAKE KANASATKA.

GENERAL SPECIFICATIONS:

DAM BOARDS	:	LENGTH 7 ⁸ 7", WIDTH 7 1/2" THICKNESS 3 1/2" WOOD
NUMBER DAM BOARDS	:	APPROX 6
WIDTH BOARD SLOT	:	6"
OPENING ABOVE BOARD	:	PRESENT OPENING 2 "
WATER LEVEL	:	PRESENT LEVEL 4 " BELOW PRESENT TOP BOARD.

IT APPEARS THAT BOARDS REST ON A CONCRETE FOOTING. HOWEVER AREA CLOSE TO BOARDS HAS ROCK.

John R. Taylor
Sandwich, N. H.
R.F.D. 1, Center Harbor
N. H. 03226

October 1, 1974

Hon. Lyle Herson
Groveton, New Hampshire

Dear Lyle:

Certainly nice seeing you at the Republican State Convention. Thought all went off well and a good time was had by all.

Reference to my conversation with you on Lake Kanastka Watershed dam and the problem we are having. Enclosed is a report on said dam and needless to say it's in bad condition. Certainly hope you can be of some help to all concerned. Kindly keep me advised.

With usual best wishes; I remain

Sincerely,
"Jack" Taylor
John R. Taylor, Treas.
Lake Kanastka Assoc. Inc.

JRT/

LIST OF AVAILABLE DATA
LAKE KANASATKA DAM
(continued)


<u>Document</u>	<u>Contents</u>	<u>Location</u>
Water Resources Board letter to Board of Selectmen, Town of Moultonboro	Notice of dam inspection dated 21 January 1975	Water Resources Board State of New Hampshire
State of New Hampshire Application for Permit to Excavate, Dredge, Fill, Mine or Construct	Application by New Hampshire Department of Public Works and Highways to perform culvert maintenance dated 26 July 1976	Water Resources Board State of New Hampshire (See Appendix pages B-7 and B-8)
Date Sheet on Lake Kanasatka, Moultonboro	Hydraulic and physical data on Lake Kanasatka Dam	Water Resources Board State of New Hampshire (See Appendix pages B-9 and B-10)


BOOK NO.	PAGE NO.
42	11
43	11
44	11
45	11
46	11
47	11
48	11
49	11
50	11
51	11
52	11
53	11
54	11
55	11
56	11
57	11
58	11
59	11
60	11
61	11
62	11
63	11
64	11
65	11
66	11
67	11
68	11
69	11
70	11
71	11
72	11
73	11
74	11
75	11
76	11
77	11
78	11
79	11
80	11
81	11
82	11
83	11
84	11
85	11
86	11
87	11
88	11
89	11
90	11
91	11
92	11
93	11
94	11
95	11
96	11
97	11
98	11
99	11
100	11

REVISIONS AFTER PROPOSAL
2017 STA. 70 STA. 71A
10-15-78 D.A.M. CHECKED BY: ARL. APPROVED.

1974-4-18	P. YAGURA
" 11-19-83	" " "
" 4-5-83	" " "
11-12-83	C. D. YAGURA
10-13-83	" " "
11-12-83	C. D. YAGURA

143







1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1485	1486	1487	1488	1489	1490	
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--

APPENDIX C - PHOTOGRAPHS

			<u>Page</u>
<u>LOCATION PLAN</u>			
Site Plan Sketch			C-1
<u>PHOTOGRAPHS</u>			
<u>No.</u>	<u>Title</u>	<u>Roll</u>	<u>Frame</u> <u>Page</u>
1.	Overview of Lake Kanasatka Dam showing downstream side	7	9A vi
2.	Drop inlet structure	7	16A C-2
3.	Area of erosion on upstream side adjacent to right wingwall	7	15A C-2
4.	Upstream side and alignment of roadway from right end of dam	7	10A C-3
5.	Area of erosion adjacent to roadway shoulder	7	11A C-3
6.	Downstream side and alignment of roadway from left end of dam	7	7A C-4
7.	Crest of embankment and Lake Kanasatka looking upstream	7	8A C-4
8.	Sluiceway outlet and dry-laid stone masonry walls	7	0 C-5
9.	Inside of box culvert looking upstream	2	16 C-5

BRUNING 44-141 25356



NOTE

PLAN DEVELOPED FROM FIELD OBSERVATIONS
MADE ON 1 NOVEMBER 1979.


LEGEND



PHOTO NUMBER AND
DIRECTION OF VIEW

HALEY & ALDRICH, INC.
CAMBRIDGE, MASSACHUSETTS

FILE NO 4454 B34




KANASATKA
(EL. 515.0)

Lake Kanasatka Dam
Moultonboro, NH

SITE PLAN SKETCH

Approx. Scale: 1" = 30'



Lake Kanasatka Dam
Moultonboro, NH

SITE PLAN SKETCH

Approx. Scale: 1" = 30' April 1980

C-1



2. Drop inlet structure



3. Area of erosion on upstream side adjacent to right wingwall




4. Upstream side and alignment of roadway from right end of dam



5. Area of erosion adjacent to roadway shoulder



6. Downstream side and alignment of roadway from left end of dam



7. Crest of embankment and Lake Kanasatka looking upstream




8. Sluiceway outlet and dry-laid stone masonry walls



9. Inside of box culvert looking upstream

APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS

<u>S</u>	<u>Page</u>
inage Area and Dam Failure Impact Area Map	D-1
<u>PUTATIONS</u>	
evations, Surface Areas, Storage Capacities, ize and Hazard Classifications and Test lood Determination	D-2
age-Discharge Relationships	D-3
age-Discharge and Storage-Elevation Curves	D-5
charge-Storage Relationships and Routing	D-6
let Works	D-7
a Failure Analysis	D-8



KANASATKA LAKE DAM
NH 00125



DRAINAGE AREA AND DAM
FAILURE IMPACT AREA MAP

APPROX. SCALE: 1" = 5200'

CLIENT HALEY & ALDRICH
 PROJECT DAM INSP.
 DETAIL LAKE KANASATKA
JOB NO. 561-10-RT-4COMPUTED BY JEDDATE CHECKED 1-30-80DATE 1/22/80CHECKED BY Joe A.PAGE NO. 1ELEVATIONS

Top of Dam El. 524.0
 D/S Toe of Dam El. 507.0
 Top of Stoplog Platform El. 519.0
 Sill of Stoplog Bay El. 511.0
 Inv. of Box Outlet El. 510.0
 Inv. of Stilling Pool El. 506.5

Top of Stoplogs at time of Inspection El. 514.1, summer elev. 515.0
 W.S. at time of Inspection El. 515.0

SURFACE AREAS (from USGS Quads)

Drainage Area = 4670 acres = 7.3 sq. mi.

Surface Area of Pond (W.S. El. 515.0) = 392 ac. ; owner reports 371 ac.
 at El. 514±

Surface Area at El. 520.0 = 467 ac.

STORAGE CAPACITIES

Max. water depth reported as 30 ft. ; Assume avg. depth = 10 ft.

Then storage at El. 514.0 = 371 ac. \times 10 ft. \times $\frac{1}{3}$ = 1237, say 1,240 ac-ft.

Storage at El. 515.0 = 1240 + $\left(\frac{371+392}{2}\right) \times 1' = 1,622$ ac-ft.

Storage at El. 524.0 = 1,622 + $\left(\frac{392+467}{2}\right) 5' + 467 \times 4' = 5,640$ ac-ft.


SIZE & HAZARD CLASSIFICATIONS

Height = 524 - 507 = 17 ft. and storage at El. 524.0 = 5,640 ac-ft.
 \therefore Size is INTERMEDIATE based on storage

Hazard is SIGNIFICANT base on Dam Failure Analysis

TEST FLOOD DETERMINATION

Intermediate size and Significant hazard, CDE give test flood range of $\frac{1}{2}$ PMF to PMF. Adopt $\frac{1}{2}$ PMF as size is at low end of size range. Since terrain is mountainous, Test Flood Inflow = 7.3 sq. mi. \times 2100 csm \times $\frac{1}{2}$ = 7,660 cfs

STAGE-DISCHARGE RELATIONSHIPSX-SECT. THRU DAM AND BOX OUTLET

Determine stage-discharge relationships for 2 conditions:

- 1) All stoplogs (summer level of elev. 515.0) in place at start of storm and not removed
- 2) Same as 1) but stoplogs removed when W.S. reaches bottom of inlet platform (elev. 516.8)

Hydraulic Controls:

- 1) & 2) a. W.S. Elev. from 515.0 to 516.8

$$Q = CLH^{3/2}; C = 3.4, L = 7.0' \therefore Q = 23.8 H^{3/2}$$

where $H = \text{W.S.} - 515.0$

- 1) b. W.S. Elev. from 516.8 to 524.0 (top of dam)

$$Q = CA\sqrt{2gH}, \text{ assume submerged orifice}$$

$$\text{let } C = 0.85; A = 1.8' \times 7.0' = 12.6 \text{ s.f.}$$

$$Q = 0.85 \times 12.6 \times \sqrt{64.4} H^{1/2}$$

$$= 86 H^{1/2}$$

$$\text{where } H = \text{W.S.} - 516.8$$

2) c W.S. Elev. from 516.8 to 520 with stoplogs removed

$$Q = C A_c \left[2g(H - \alpha V_1^2/2g - d_c - h_{f,2}) \right]^{1/2}; \text{ Inlet Control}$$

assume: $\alpha V_1^2/2g$ and $h_{f,2}$ to be negligible

$$d_c \approx 2/3 H$$

$$\text{then } Q = C A_c \left[2g(H - 2/3 H) \right]^{1/2} = C A_c \left[2/3 g H \right]^{1/2}$$

$$\text{let } C = 0.85; A_c = d_c \times (W = 7') = 2/3 H \times 7 = 4.67 H$$

$$\therefore Q = 0.85 \times 4.67 H \left(2/3 \times 32.2 \times H \right)^{1/2} = 3.97 H (21.5 H)^{1/2}$$

$$= 3.97 H (21.5)^{1/2} H^{1/2} = 18.4 H^{3/2}$$

$$\text{where } H = \text{W.S. Elev.} - 511.0$$

2) d W.S. Elev. from 520 to 524 with stoplogs removed


$$Q = C A \sqrt{2gH} = C A \sqrt{2g} \sqrt{H}$$

$$\text{let } C = 0.85; A = 7' \times 5.8' = 40.6 \text{ s.f.}$$

$$\text{then } Q = 0.85 \times 40.6 \times (64.4)^{1/2} H^{1/2} = 277 H^{1/2}$$

$$\text{where } H = \text{W.S. El.} - 516.8$$

W.S. ELEV.	STOPLOGS TO ELEV. 515.0, NONE REMOVED				STOPLOGS TO ELEV. 515.0, REMOVED @ W.S. ELEV. 516.8			
	H	Q (cfs)(a)	H	Q (cfs)(b)	H	Q (cfs)(c)	H	Q (cfs)(d)
515.0	0	0	-		0	0		
515.5	0.5	8	-		0.5	8		
516.0	1.0	24	-		1.0	24		
516.8	1.8	57	0		1.8/5.8	57/257	-	
518.0	N/A		1.2	94	7	341	N/A	
520.0	N/A		3.2	154	9	497	3.2	496
522.0	N/A		5.2	196	N/A		5.2	632
524.0	N/A		7.2	231	N/A		7.2	743



CLIENT HALEY & ALDRICH
 PROJECT DAM INSP.
 DETAIL LAKE KANASATKA
JOB NO. 561-10-RT-4DATE CHECKED 3-19-80CHECKED BY Joe A.COMPUTED BY JEDDATE 3/18/80PAGE NO. 5SURCHARGE-STORAGE RELATIONSHIPS

Estimated total volume of R.O. during test flood
 $= 9.5" \times \frac{1 \text{ ft.}}{12"} \times (\text{D.A.} = 4670 \text{ acres}) = 3,700 \text{ ac-ft}$

Since available storage between winter pool (El. 514.0) and top of dam (El. 524.0) = 4,400 ac-ft. and between summer pool (El. 515.0) and top of dam = 4,020 ac-ft, the dam will not be overtopped by the test flood.

Since a continuous outflow would be occurring during the test flood event, surcharge-storage routing must be performed to determine the actual stages.

SURCHARGE-STORAGE ROUTING

Use graphical solution:

Since $Q_{P2} = Q_{P1} (1 - \text{STOR}/\text{R.O.})$

then $\text{STOR} = (\text{R.O.}) (1 - Q_{P2}/Q_{P1})$

$= (9.5") (1 - Q_{P2}/7660)$

$Q_{P2}(\text{cfs})$	STOR.(in.)	STOR.(ac-ft.)	ELEV.
100	9.38	3650	523.17
300	9.13	3550	522.95
500	8.88	3460	522.75
700	8.63	3360	522.50

Plotting the above points (Q_{P2} vs Elev.) on the stage Discharge Curve results in the following:

	<u>Stoplogs</u> <u>Remain</u>	<u>Stoplogs</u> <u>Removed</u>
Test Flood Outflow :	215 cfs	665 cfs
Test Flood Pond El. :	523.05	522.54
Test Flood Surch.-Stor. :	3600 ac-ft.	3380 ac-ft.

OUTLET WORKS

Determine discharge capacity if all stoplogs are removed with pond at summer pool elev. 515.0

Assume control to be at inlet to box culvert,

$$\text{then } Q = C A_c \left[2g (H - \alpha V_1^2 / 2g - d_c - h_{f,1.2}) \right]^{1/2}$$

from page 3, $Q = 18.4 H^{3/2}$ where $H = W.S. - El. 511.0$

$$\therefore Q = 18.4 (515 - 511)^{3/2} = 150 \text{ cfs}$$

Check if $S_c < S_o$ where $S_o = 0.02$

$$S_c = (Q/K_c)^2 \text{ where } Q = 150 \text{ cfs}$$

and

$$K_c = (1.49/n) R^{2/3} A_c$$

$$n = 0.015$$

$$A_c = 7' \times d_c = 7 \times 2/3 H$$

$$= 7 \times 2/3 \times 4 = 18.67$$

$$R = A_c/P = 18.67/(7 + 2d_c)$$

$$= 18.67/12.33 = 1.51$$

$$\text{then } K_c = (1.49/0.015) (1.51)^{2/3} (18.67) = 2,444$$

$$\therefore S_c = (150/2444)^2 = 0.0038$$

Since $(S_c = 0.0038) < (S_o = 0.02)$, the assumption of critical depth at inlet is correct

DAM FAILURE ANALYSIS

Top of Dam El. 524.0 } H_t = 524 - 507 = 17 ft.
Toe of Dam El. 507.0 }

Length of Dam at mid-height ≈ 100 ft.

$$\text{then } Q_f = 8/27 W_b \sqrt{g} Y_o^{3/2}$$

$$= 8/27 (0.4 \times 100) (32.2)^{1/2} (17)^{3/2} = 4,700 \text{ cfs}$$

Project discharge prior to failure:
Inlet control submerged orifice

$$\text{then } Q_o = CA \sqrt{2gH} \quad \text{where } C = 0.85$$

$$A = 7.0 \times 5.8' = 40.6 \text{ s.f.}$$


$$H = 524 - 516.8 = 7.2'$$

± Crown of inlet

$$\therefore Q_o = 0.85 (40.6) (64.4 \times 7.2)^{1/2} = 1743 \text{ cfs}$$

$$\text{then } Q_p = 1740 + 4700 = 5440 \text{ cfs}$$

Determine Stage-Discharge Relationship of
D/S Channel:



TYP. D/S CHANNEL X-SECT.

W.S. ELEV.	AREA (s.f.)	R	FLOW (cfs)
504	40	1.857	130
506	225	1.087	510
508	820	2.090	2,850
510	1765	3.055	7,910

D/S W.S. prior to failure:

$$Q_p = 740 \text{ cfs}$$
$$\text{W.S. El.} = \frac{740 - 510}{2850 - 510} \times 2 + 506 = 506.2$$

D/S W.S. after failure:

$$Q_p = 5,440 \text{ cfs}$$
$$\text{W.S. El.} = \frac{5440 - 2850}{7910 - 2850} \times 2 + 508 = 509.0$$

Based on the field observations, a flow of 740 cfs would have no significant effect on existing development. However, in the event of a dam failure, at the end of the gravel road, on the shore of Lake Winnepesaukee, there are 2 to 3 homes which would experience shallow depth - high velocity flooding. Furthermore, future development between the gravel road and the d/s channel appears likely. Therefore, potential hazard in the event of a dam failure is considered to be significant.

APPENDIX E - INFORMATION AS CONTAINED IN THE
NATIONAL INVENTORY OF DAMS

NOT AVAILABLE AT THIS TIME

END

FILMED

8-85

DTIC